

ANNEXURE FOR RFP FOR CIVIL/PLUMBING WORK AT HEAD OFFICE-ANNEX, DHARWAD

WALLS									PLASTERING					PAINTING				
SL NO	ITEMS	UNIT	NOS	LENGTH	WIDTH	HEIGHT	QUANTITY	TOTAL QTY	NOS	LENGTH	HEIGHT	QUANTITY	TOTAL QTY	NOS	LENGTH	HEIGHT	QUANTITY	TOTAL QTY
1	LIFT ALL FLOORS																	
	EARTH WORK FOR LIFT	CFT	1	8.00	8.00	7.00	448.00	448.00										
	LIFT BED CONCRETE (M10)	CFT	1	8.00	8.00	0.50	32.00	32.00										
	LIFT FLOORING CONCRETE (M20)	CFT	1	8.00	8.00	1.50	96.00	96.00	1.00	8.00	8.00	64.00	64.00					
	LIFT RCC WALL CONCRETE (M20)	CFT	2	8.00	0.66	5.50	58.08	58.08	4.00	6.50	5.50	143.00	143.00	4.00	6.50	5.50	143.00	143.00
		CFT	2	6.50	0.66	5.50	47.19	47.19										
	TOTAL							105.27					207.00					143.00
	LIFT RCC COLUMNS CONCRETE (M20)	CFT	4	1.00	0.66	40.00	105.60	105.60										
	LIFT RCC LINTEL CONCRETE (M20)	CFT	4	7.50	0.66	0.66	13.07	13.07										
	LIFT RCC BEAM CONCRETE (M20)	CFT	4	29.00	0.66	1.00	76.56	76.56										
	PLINTH BEAM CONCRETE (M20)	CFT					1.00	1.00										
	LIFT RCC WALL, FLOORING & RCC COLUMNS, RCC BEAM, RCC LINTEL STEEL REINFORCEMENT	KG					1100.00	1100.00										
	8" CEMENT BLOCK WALL IN (1:4) CEMENT MORTER																	
	LIFT WALL - FRONT SIDE	SFT	1	8.00	1.00	38.00	304.00	304.00	2.00	8.00	38.00	608.0	608.0	1.00	8.00	38.00	304.0	304.0
	LIFT WALL - SIDE	SFT	1	8.00	1.00	38.00	304.00	304.00	2.00	8.00	38.00	608.0	608.0	2.00	8.00	38.00	608.0	608.0
	LIFT WALL - SIDE	SFT	1	8.00	1.00	38.00	304.00	304.00	2.00	8.00	38.00	608.0	608.0	2.00	8.00	38.00	608.0	608.0
	LIFT WALL - BACK SIDE	SFT	1	8.00	1.00	38.00	304.00	304.00	2.00	8.00	38.00	608.0	608.0	2.00	8.00	38.00	608.0	608.0
	DOOR LESS	SFT	-3	3.00	1.00	7.00	-63.00	-63.00	-6.00	3.00	7.00	-126.0	-126.0	-6.00	3.00	7.00	-126.0	-126.0
	TOTAL OF 8" CEMENT BLOCK WALL IN (1:4) CEMENT MORTER AT LIFT							1153.00					2306.00					2002.00
	GROUND FLOOR																	
	EARTH WORK FOR RCC PLINTH BEAM FOR 6" CEMENT BLOCK WALL IN (1:4) CEMENT MORTER	CFT	1	160.00	1.50	2.00	480.00	480.00										
	PCC BED (M-10) FOR RCC PLINTH BEAM FOR 6" CEMENT BLOCK WALL IN (1:4) CEMENT MORTER	CFT	1	160.00	1.50	0.33	79.20	79.20										
	SIZE STONE MASONARY	CFT	1	160.00	1.50	2.00	480.00	480.00										
	RCC (M-20) PLINTH BEAM FOR 6" CEMENT BLOCK WALL IN (1:4) CEMENT MORTER	CFT	1	160.00	0.66	1.50	158.40	158.40										
	M-20 FOR DINING HALL	CFT					762.06	762.06										
	6" CEMENT BLOCK WALL IN (1:4) CEMENT MORTER																	
1	KITCHEN WALL	SFT	1	11.68	1.00	10.00	116.75	116.75	2.00	11.68	10.00	233.5	233.5	1.00	11.68	10.00	116.8	116.8
														1.00	11.68	5.00	58.4	58.4
	STORE ROOM WALL	SFT	1	11.68	1.00	10.00	116.75	116.75	2.00	11.68	10.00	233.5	233.5	1.00	11.68	10.00	116.8	116.8
														1.00	11.68	5.00	58.4	58.4
	DOOR LESS	SFT	-1	4.00	1.00	7.00	-28.00	-28.00	-2.00	4.00	7.00	-56.0	-56.0	-2.00	4.00	7.00	-56.0	-56.0
	DINING WALL	SFT	1	18.08	1.00	11.00	198.92	198.92	2.00	18.08	11.00	397.8	397.8	2.00	18.08	11.00	397.8	397.8
	DINING WALL	SFT	1	16.00	1.00	11.00	176.00	176.00	2.00	16.00	11.00	352.0	352.0	2.00	16.00	11.00	352.0	352.0
	DINING WALL	SFT	1	2.08	1.00	11.00	22.91	22.91	2.00	2.08	11.00	45.8	45.8	1.00	2.08	11.00	22.9	22.9
	WINDOW LESS	SFT	-2	5.00	1.00	4.50	-45.00	-45.00	-2.00	5.00	4.50	-45.0	-45.0	-2.00	5.00	4.50	-45.0	-45.0
	DINING WALL SUPPORTING PLATFORMS	SFT	10	2.00	1.00	3.00	60.00	60.00	2.00	2.00	3.00	12.0	12.0	2.00	2.00	3.00	12.0	12.0
	ENTRANCE LOBBY WALL	SFT	1	14.33	1.00	10.00	143.30	143.30	2.00	14.33	10.00	286.6	286.6	2.00	14.33	11.00	315.3	315.3
	DOOR LESS	SFT	-1	8.00	1.00	8.00	-64.00	-64.00	-2.00	8.00	8.00	-128.0	-128.0	-2.00	8.00	8.00	-128.0	-128.0
	GENTS TOILET WALL	SFT	1	13.08	1.00	10.00	130.83	130.83	2.00	13.08	10.00	261.7	261.7	1.00	13.08	10.00	130.8	130.8
														1.00	13.08	5.00	65.4	65.4
		SFT	1	4.71	1.00	9.50	44.73	44.73	2.00	4.71	9.50	89.5	89.5	2.00	4.71	4.50	42.4	42.4
		SFT	1	4.71	1.00	9.50	44.73	44.73	2.00	4.71	9.50	89.5	89.5	2.00	4.71	4.50	42.4	42.4
		SFT	1	4.00	1.00	9.50	38.00	38.00	2.00	4.00	9.50	76.0	76.0	2.00	4.00	4.50	36.0	36.0
	DOOR LESS	SFT	-1	2.50	1.00	7.00	-17.50	-17.50	-2.00	2.50	7.00	-35.0	-35.0	-2.00	2.50	2.00	-10.0	-10.0
	LADIES TOILET WALL	SFT	1	11.68	1.00	10.00	116.75	116.75	2.00	11.68	10.00	233.5	233.5	1.00	11.68	10.00	116.8	116.8
														1.00	11.68	5.00	58.4	58.4
		SFT	1	8.50	1.00	9.50	80.75	80.75	2.00	8.50	9.50	161.5	161.5	2.00	8.50	4.50	76.5	76.5
		SFT	1	5.00	1.00	9.50	47.50	47.50	2.00	5.00	9.50	95.0	95.0	2.00	5.00	4.50	45.0	45.0
		SFT	1	5.00	1.00	9.50	47.50	47.50	2.00	5.00	9.50	95.0	95.0	2.00	5.00	4.50	45.0	45.0
	DOOR LESS	SFT	-2	2.50	1.00	7.00	-35.00	-35.00	-4.00	2.50	7.00	-70.0	-70.0	-4.00	2.50	2.00	-20.0	-20.0
	AT REMOVED WINDOW	SFT	3	4.75	1.00	5.00	71.25	71.25	2.00	4.75	5.00	47.5	47.5	2.00	4.75	4.50	42.8	42.8
	AT REMOVED DOOR	SFT	2	3.50	1.00	7.00	49.00	49.00	2.00	3.50	7.00	49.0	49.0	2.00	3.50	4.50	31.5	31.5
	TOTAL							1316.17					2425.34					1924.13
	FIRST FLOOR																	
	6" CEMENT BLOCK WALL IN (1:4) CEMENT MORTER																	
	STAFF TOILET WALL	SFT	1	13.13	1.00	11.00	144.38	144.38	2.00	13.13	11.00	288.8	288.8	1.00	13.13	11.00	144.4	144.4
														1.00	13.08	6.00	78.5	78.5
		SFT	1	7.33	1.00	9.50	69.64	69.64	2.00	7.33	9.50	139.3	139.3	2.00	7.33	4.50	66.0	66.0
	DOOR LESS	SFT	-1	2.50	1.00	7.00	-17.50	-17.50	-2.00	2.50	7.00	-35.0	-35.0	-2.00	2.50	2.00	-10.0	-10.0
	GENTS TOILET & LADIES TOILET WALL	SFT	1	12.68	1.00	11.00	139.43	139.43	2.00	12.68	11.00	278.9	278.9	1.00	12.68	11.00	139.4	139.4
														1.00	12.68	6.00	76.1	76.1
		SFT	1	5.21	1.00	9.50	49.48	49.48	2.00	5.21	9.50	99.0	99.0	2.00	5.21	4.50	46.9	46.9
		SFT	1	5.50	1.00	9.50	52.25	52.25	2.00	5.50	9.50	104.5	104.5	2.00	5.50	4.50	49.5	49.5
		SFT	1	4.50	1.00	9.50	42.75	42.75	2.00	4.50	9.50	85.5	85.5	2.00	4.50	4.50	40.5	40.5
		SFT	1	6.16	1.00	9.50	58.52	58.52	2.00	6.16	9.50	117.0	117.0	2.00	6.16	4.50	55.4	55.4
		SFT	1	2.00	1.00	9.50	19.00	19.00	2.00	2.00	9.50	38.0	38.0	2.00	2.00	4.50	18.0	18.0
		SFT	1	5.50	1.00	9.50	52.25	52.25	2.00	5.50	9.50	104.5	104.5	2.00	5.50	4.50	49.5	49.5
		SFT	1	8.71	1.00	9.50	82.73	82.73	2.00	8.71	9.50	165.5	165.5	2.00	8.71	4.50	78.4	78.4
		SFT	1	8.71	1.00	11.00	95.79	95.79	2.00	8.71	11.00	191.6	191.6	1.00	8.71	11.00	95.8	95.8

															1.00	8.71	6.00	52.3	52.3
	LIBRARY	SFT	1	3.67	1.00	11.00	40.37	40.37	2.00	3.67	11.00	80.7	80.7		1.00	3.67	11.00	40.4	40.4
															1.00	3.67	6.00	22.0	22.0
	LONGE	SFT	0	20.08	1.00	11.00	0.00	0.00	0.00	20.08	11.00	0.0	0.0		0.00	20.08	11.00	0.0	0.0
	DOOR LESS	SFT	0	4.00	1.00	7.00	0.00	0.00	0.00	4.00	7.00	0.0	0.0		0.00	4.00	7.00	0.0	0.0
	DOOR LESS	SFT	-3	2.50	1.00	7.00	-52.50	-52.50	-6.00	2.50	7.00	-105.0	-105.0		-6.00	2.50	2.00	-30.0	-30.0
	AT REMOVED WINDOW	SFT	3	4.75	1.00	5.00	71.25	71.25	2.00	4.75	5.00	47.5	47.5		2.00	4.75	4.50	42.8	42.8
	TOTAL							847.83					1600.65						1055.69
	SECOND FLOOR																		
	6" CEMENT BLOCK WALL IN (1:4) CEMENT MORTER																		
	GENTS TOILET & LADIES TOILET WALL	SFT	1	16.00	1.00	11.00	176.00	176.00	2.00	16.00	11.00	352.0	352.0		1.00	16.00	11.00	176.0	176.0
															1.00	16.00	6.00	96.0	96.0
		SFT	1	5.21	1.00	9.50	49.48	49.48	2.00	5.21	9.50	99.0	99.0		2.00	5.21	4.50	46.9	46.9
		SFT	1	5.50	1.00	9.50	52.25	52.25	2.00	5.50	9.50	104.5	104.5		2.00	5.50	4.50	49.5	49.5
		SFT	1	4.50	1.00	9.50	42.75	42.75	2.00	4.50	9.50	85.5	85.5		2.00	4.50	4.50	40.5	40.5
		SFT	1	6.16	1.00	9.50	58.52	58.52	2.00	6.16	9.50	117.0	117.0		2.00	6.16	4.50	55.4	55.4
		SFT	1	2.00	1.00	9.50	19.00	19.00	2.00	2.00	9.50	38.0	38.0		2.00	2.00	4.50	18.0	18.0
		SFT	1	5.50	1.00	9.50	52.25	52.25	2.00	5.50	9.50	104.5	104.5		2.00	5.50	4.50	49.5	49.5
		SFT	1	8.71	1.00	9.50	82.73	82.73	2.00	8.71	9.50	165.5	165.5		2.00	8.71	4.50	78.4	78.4
		SFT	1	8.71	1.00	11.00	95.79	95.79	2.00	8.71	11.00	191.6	191.6		1.00	8.71	11.00	95.8	95.8
															1.00	8.71	6.00	52.3	52.3
	LIBRARY	SFT	1	3.67	1.00	11.00	40.37	40.37	2.00	3.67	11.00	80.7	80.7		1.00	3.67	11.00	40.4	40.4
															1.00	3.67	6.00	22.0	22.0
	LIBRARY	SFT	0	20.08	1.00	11.00	0.00	0.00	0.00	20.08	11.00	0.0	0.0		0.00	20.08	11.00	0.0	0.0
	DOOR LESS	SFT	0	4.00	1.00	7.00	0.00	0.00	0.00	4.00	7.00	0.0	0.0		0.00	4.00	7.00	0.0	0.0
	DOOR LESS	SFT	-3	2.50	1.00	7.00	-52.50	-52.50	-6.00	2.50	7.00	-105.0	-105.0		-6.00	2.50	2.00	-30.0	-30.0
	AT REMOVED WINDOW	SFT	3	4.75	1.00	5.00	71.25	71.25	2.00	4.75	5.00	47.5	47.5		2.00	4.75	4.50	42.8	42.8
	TOTAL							687.89					1280.78						833.37
	TOTAL OF 6" CEMENT BLOCK WALL IN (1:4) CEMENT MORTER AT GF,FF,SF							2851.88					5306.77						3813.19

DOORS & VENTILATORS										
SL NO	ITEMS	UNIT	NOS	LENGTH	WIDTH	DEPTH	QUANTITY	TOTAL QTY		
A	DOORS									
1	DOOR WITH MS COLLAPSIBLE SLIDING SHUTTER									
a	1 NOS. 8' X 8'									
a	GROUND FLOOR MAIN DOOR AT ENTRANCE	SFT	1	8.00	1.00	8.00	64.00	64.00		
2	MS DOOR									
b	1 NOS. 4' X 7'									
	GF KITCHEN BACKSIDE	SFT	1	4.00	1.00	7.00	28.00	28.00		
c	1 NOS. 4' X 7'									
	GF STORE ROOM	SFT	1	4.00	1.00	7.00	28.00	28.00		
4	DOOR WITH WPC SHUTTER & FRAME									
a	GF GENTS TOILET	SFT	1	3.00	1.00	7.00	21.00	21.00		
b	GF GENTS TOILET	SFT	1	2.50	1.00	7.00	17.50	17.50		
c	GF LADIES TOILET	SFT	1	3.00	1.00	7.00	21.00	21.00		
d	GF LADIES TOILET	SFT	2	2.50	1.00	7.00	35.00	35.00		
e	FF STAFF TOILET	SFT	1	2.50	1.00	7.00	17.50	17.50		
f	FF LADIES TOILET	SFT	2	2.50	1.00	7.00	35.00	35.00		
g	FF GENTS TOILET	SFT	1	2.50	1.00	7.00	17.50	17.50		
h	SF LADIES TOILET	SFT	2	2.50	1.00	7.00	35.00	35.00		
i	SF GENTS TOILET	SFT	1	2.50	1.00	7.00	17.50	17.50		
	10 NOS. 2'6" X 7'									
	2 NOS. 3' X 7'									
	TOTAL OF DOOR							217.00		
1	UPVC WINDOWS & VENTILATOR									
a	GF DINING HALL WINDOW	SFT	2	5.00	4.00	1.00	40.00	40.00		
b	GF NEAR HAND WASH WINDOW	SFT	1	3.50	4.00	1.00	14.00	14.00		
c	GF GENTS TOILET VENTILATOR	SFT	1	2.50	2.00	1.00	5.00	5.00		
d	GF LADIES TOILET VENTILATOR	SFT	3	2.50	2.00	1.00	15.00	15.00		
e	FF STAFF TOILET VENTILATOR	SFT	1	2.50	2.00	1.00	5.00	5.00		
f	FF LADIES TOILET VENTILATOR	SFT	3	2.50	2.00	1.00	15.00	15.00		
g	FF GENTS TOILET VENTILATOR	SFT	2	2.50	2.00	1.00	10.00	10.00		
h	SF LADIES TOILET VENTILATOR	SFT	3	2.50	2.00	1.00	15.00	15.00		
i	SF GENTS TOILET VENTILATOR	SFT	2	2.50	2.00	1.00	10.00	10.00		
	WINDOWS : 2 NOS. 5' X 4'		18					40.00		
	WINDOWS : 1 NOS. 3'6" X 4'							14.00		
	VENTILATOR : 15 NOS. 2'6" X 2'							75.00		
	TOTAL OF UPVC WINDOWS & VENTILATOR							129.00		

TOILET FLOORING & WALL TILES, KITCHEN WALL TILES & LIFT WALL TILES, DINING HALL FLOORING														
SL NO	ITEMS	UNIT	NOS	LENGTH	WIDTH	DEPTH	QUANTITY	TOTAL QTY	TOILET		KITCHEN		LIFT	DINING HALL
									FLOORING	WALL TILES	FLOORING	WALL TILES	WALL TILES	FLOORING
	GROUND FLOOR													
	DINING HALL						1524.12	1524.12						1524.12
	KITCHEN													
	WALL TILES	SFT	1	1.58	1.00	5.00	7.92	7.92						
		SFT	2	1.16	1.00	5.00	11.60	11.60						
		SFT	1	1.13	1.00	5.00	5.63	5.63						
		SFT	1	6.42	1.00	5.00	32.08	32.08						
		SFT	1	0.79	1.00	5.00	3.96	3.96						
		SFT	1	0.83	1.00	5.00	4.17	4.17						
		SFT	1	0.75	1.00	5.00	3.75	3.75						
		SFT	1	2.79	1.00	5.00	13.96	13.96						
		SFT	1	11.68	1.00	5.00	58.38	58.38						
		SFT	1	2.71	1.00	5.00	13.54	13.54						
		SFT	2	0.83	1.00	5.00	8.33	8.33						
		SFT	1	0.88	1.00	5.00	4.38	4.38						

		SFT	1	14.72	1.00	5.00	73.58	73.58						
		SFT	1	6.59	1.00	5.00	32.96	32.96						
		SFT	1	2.00	1.00	5.00	10.00	10.00						
		SFT	1	1.55	1.00	5.00	7.75	7.75						
	TOTAL							291.97				291.97		
	GROUND FLOOR													
A	GENTS TOILET													
1	FLOORING	SFT	1	4.00	4.21	1.00	16.83	16.83	16.83					
	FLOORING	SFT	1	2.50	0.52	1.00	1.29	1.29	1.29					
	WALL TILES	SFT	1	4.71	1.00	5.00	23.54	23.54		23.54				
	WALL TILES	SFT	1	4.00	1.00	5.00	20.00	20.00		20.00				
	WALL TILES	SFT	1	4.21	1.00	5.00	21.04	21.04		21.04				
	WALL TILES	SFT	1	1.50	1.00	5.00	7.50	7.50		7.50				
	WALL TILES	SFT	1	0.52	1.00	5.00	2.58	2.58		2.58				
	URINAL													
2	FLOORING	SFT	1	4.92	4.71	1.00	23.15	23.15	23.15					
	WALL TILES	SFT	1	4.92	1.00	5.00	24.58	24.58		24.58				
	WALL TILES	SFT	2	4.71	1.00	5.00	47.08	47.08		47.08				
	WASH BASIN AREA													
3	FLOORING	SFT	1	9.92	2.75	1.00	27.27	27.27	27.27					
	WALL TILES	SFT	1	9.92	1.00	5.00	49.58	49.58		49.58				
	WALL TILES	SFT	1	2.00	1.00	5.00	10.00	10.00		10.00				
	WALL TILES	SFT	1	2.75	1.00	5.00	13.75	13.75		13.75				
	PASSAGE													
4	FLOORING	SFT	1	7.46	3.16	1.00	23.57	23.57	23.57					
	FLOORING	SFT	1	0.83	3.00	1.00	2.50	2.50	2.50					
	WALL TILES	SFT	1	4.71	1.00	5.00	23.54	23.54		23.54				
	WALL TILES	SFT	1	4.46	1.00	5.00	22.29	22.29		22.29				
	WALL TILES	SFT	2	3.16	1.00	5.00	31.60	31.60		31.60				
	WALL TILES	SFT	2	0.83	1.00	5.00	8.33	8.33		8.33				
B	LADIES TOILET													
1	FLOORING	SFT	1	5.00	3.75	1.00	18.75	18.75	18.75					
	FLOORING	SFT	1	2.50	0.50	1.00	1.25	1.25	1.25					
	WALL TILES	SFT	1	5.50	1.00	5.00	27.50	27.50		27.50				
	WALL TILES	SFT	1	3.75	1.00	5.00	18.75	18.75		18.75				
	WALL TILES	SFT	1	5.00	1.00	5.00	25.00	25.00		25.00				
	WALL TILES	SFT	1	1.25	1.00	5.00	6.25	6.25		6.25				
	WALL TILES	SFT	1	0.50	1.00	5.00	2.50	2.50		2.50				
2	FLOORING	SFT	1	5.00	3.75	1.00	18.75	18.75	18.75					
	FLOORING	SFT	1	2.50	0.50	1.00	1.25	1.25	1.25					
	WALL TILES	SFT	1	5.50	1.00	5.00	27.50	27.50		27.50				
	WALL TILES	SFT	1	3.75	1.00	5.00	18.75	18.75		18.75				
	WALL TILES	SFT	1	5.00	1.00	5.00	25.00	25.00		25.00				
	WALL TILES	SFT	1	1.25	1.00	5.00	6.25	6.25		6.25				
	WALL TILES	SFT	1	0.50	1.00	5.00	2.50	2.50		2.50				
	WASH BASIN AREA													
3	FLOORING	SFT	1	11.68	4.50	1.00	52.54	52.54	52.54					
	WALL TILES	SFT	1	11.68	1.00	5.00	58.38	58.38		58.38				
	WALL TILES	SFT	2	1.25	1.00	5.00	12.50	12.50		12.50				
	WALL TILES	SFT	1	0.50	1.00	5.00	2.50	2.50		2.50				
	WALL TILES	SFT	2	4.50	1.00	5.00	45.00	45.00		45.00				
	WASH BASIN AREA													
4	FLOORING	SFT	1	5.50	3.18	1.00	17.46	17.46	17.46					
	FLOORING	SFT	1	3.00	0.92	1.00	2.75	2.75	2.75					
	WALL TILES	SFT	1	5.50	1.00	5.00	27.50	27.50		27.50				
	WALL TILES	SFT	1	4.09	1.00	5.00	20.46	20.46		20.46				
	WALL TILES	SFT	1	2.50	1.00	5.00	12.50	12.50		12.50				
	DINNING WASH BASIN AREA													
	WALL TILES	SFT	1	12.00	1.00	2.00	24.00	24.00		24.00				
	TOTAL							875.62	207.36	668.26	0.00	0.00	0.00	1524.12
	FIRST FLOOR													
A	STAFF TOILET													
1	FLOORING	SFT	1	7.33	4.96	1.00	36.34	36.34	36.34					
	FLOORING	SFT	1	2.50	0.50	1.00	1.25	1.25	1.25					
	WALL TILES	SFT	1	7.33	1.00	5.00	36.65	36.65		36.65				
	WALL TILES	SFT	1	4.96	1.00	5.00	24.79	24.79		24.79				
	WALL TILES	SFT	1	5.50	1.00	5.00	27.50	27.50		27.50				
	WALL TILES	SFT	1	4.83	1.00	5.00	24.15	24.15		24.15				
	WALL TILES	SFT	1	0.50	1.00	5.00	2.50	2.50		2.50				
	WASH BASIN AREA													
2	FLOORING	SFT	1	7.67	7.33	1.00	56.22	56.22	56.22					
	WALL TILES	SFT	2	7.67	1.00	5.00	76.70	76.70		76.70				
	WALL TILES	SFT	1	4.83	1.00	5.00	24.15	24.15		24.15				
	WALL TILES	SFT	1	3.50	1.00	5.00	17.50	17.50		17.50				
	WALL TILES	SFT	0	0.50	1.00	5.00	0.00	0.00		0.00				
B	GENTS TOILET													
1	FLOORING	SFT	1	5.50	4.50	1.00	24.75	24.75	24.75					
	FLOORING	SFT	1	2.50	0.50	1.00	1.25	1.25	1.25					
	WALL TILES	SFT	1	5.50	1.00	5.00	27.50	27.50		27.50				
	WALL TILES	SFT	1	4.50	1.00	5.00	22.50	22.50		22.50				
	WALL TILES	SFT	1	5.00	1.00	5.00	25.00	25.00		25.00				
	WALL TILES	SFT	1	3.00	1.00	5.00	15.00	15.00		15.00				
	WALL TILES	SFT	1	0.50	1.00	5.00	2.50	2.50		2.50				
	URINALS													
2	FLOORING	SFT	1	4.46	5.83	1.00	25.99	25.99	25.99					
	WALL TILES	SFT	1	4.46	1.00	5.00	22.29	22.29		22.29				
	WALL TILES	SFT	1	5.83	1.00	5.00	29.15	29.15		29.15				
	WALL TILES	SFT	1	3.00	1.00	5.00	15.00	15.00		15.00				
	WALL TILES	SFT	1	2.00	1.00	5.00	10.00	10.00		10.00				
	WASH BASIN AREA													
3	FLOORING	SFT	1	6.51	6.00	1.00	39.05	39.05	39.05					
	WALL TILES	SFT	2	6.51	1.00	5.00	65.08	65.08		65.08				
	WALL TILES	SFT	1	1.50	1.00	5.00	7.50	7.50		7.50				
	WALL TILES	SFT	1	2.00	1.00	5.00	10.00	10.00		10.00				
	WALL TILES	SFT	1	2.58	1.00	5.00	12.92	12.92		12.92				
	WALL TILES	SFT	2	0.50	1.00	5.00	5.00	5.00		5.00				
C	LADIES TOILET													
1	FLOORING	SFT	1	4.50	4.00	1.00	18.00	18.00	18.00					

2399.74

	FLOORING	SFT	1	2.50	0.50	1.00	1.25	1.25	1.25								
	WALL TILES	SFT	1	4.00	1.00	5.00	20.00	20.00		20.00							
	WALL TILES	SFT	1	5.00	1.00	5.00	25.00	25.00		25.00							
	WALL TILES	SFT	1	4.50	1.00	5.00	22.50	22.50		22.50							
	WALL TILES	SFT	1	0.50	1.00	5.00	2.50	2.50		2.50							
	WALL TILES	SFT	1	1.50	1.00	5.00	7.50	7.50		7.50							
	TOILET																
2	FLOORING	SFT	1	5.00	4.21	1.00	21.04	21.04	21.04								
	FLOORING	SFT	1	2.50	0.50	1.00	1.25	1.25	1.25								
	WALL TILES	SFT	1	5.00	1.00	5.00	25.00	25.00		25.00							
	WALL TILES	SFT	1	4.21	1.00	5.00	21.04	21.04		21.04							
	WALL TILES	SFT	1	4.50	1.00	5.00	22.50	22.50		22.50							
	WALL TILES	SFT	1	0.50	1.00	5.00	2.50	2.50		2.50							
	WALL TILES	SFT	1	2.00	1.00	5.00	10.00	10.00		10.00							
	WASH BASIN AREA																
3	FLOORING	SFT	1	8.71	4.00	1.00	34.83	34.83	34.83								
	WALL TILES	SFT	1	8.71	1.00	5.00	43.54	43.54		43.54							
	WALL TILES	SFT	1	4.00	1.00	5.00	20.00	20.00		20.00							
	WALL TILES	SFT	1	1.00	1.00	5.00	5.00	5.00		5.00							
	WALL TILES	SFT	1	0.50	1.00	5.00	2.50	2.50		2.50							
	WALL TILES	SFT	1	1.50	1.00	5.00	7.50	7.50		7.50							
	WALL TILES	SFT	1	2.00	1.00	5.00	10.00	10.00		10.00							
	WASH BASIN AREA																
4	FLOORING	SFT	1	6.51	3.50	1.00	22.78	22.78	22.78								
	WALL TILES	SFT	1	6.51	1.00	5.00	32.54	32.54		32.54							
	WALL TILES	SFT	1	3.50	1.00	5.00	17.50	17.50		17.50							
	WALL TILES	SFT	1	3.51	1.00	5.00	17.54	17.54		17.54							
	TOTAL						1102.06	284.01	818.05	0.00	0.00	0.00	0.00				1102.06
	SECOND FLOOR																
A	GENTS TOILET																
1	FLOORING	SFT	1	5.50	4.50	1.00	24.75	24.75	24.75								
	FLOORING	SFT	1	2.50	0.50	1.00	1.25	1.25	1.25								
	WALL TILES	SFT	1	5.50	1.00	5.00	27.50	27.50		27.50							
	WALL TILES	SFT	1	4.50	1.00	5.00	22.50	22.50		22.50							
	WALL TILES	SFT	1	5.00	1.00	5.00	25.00	25.00		25.00							
	WALL TILES	SFT	1	3.00	1.00	5.00	15.00	15.00		15.00							
	WALL TILES	SFT	1	0.50	1.00	5.00	2.50	2.50		2.50							
	TOILET																
2	FLOORING	SFT	1	4.46	5.83	1.00	25.99	25.99	25.99								
	WALL TILES	SFT	1	4.46	1.00	5.00	22.29	22.29		22.29							
	WALL TILES	SFT	1	5.83	1.00	5.00	29.15	29.15		29.15							
	WALL TILES	SFT	1	3.00	1.00	5.00	15.00	15.00		15.00							
	WALL TILES	SFT	1	2.00	1.00	5.00	10.00	10.00		10.00							
	WASH BASIN AREA																
3	FLOORING	SFT	1	6.51	6.00	1.00	39.05	39.05	39.05								
	WALL TILES	SFT	2	6.51	1.00	5.00	65.08	65.08		65.08							
	WALL TILES	SFT	1	1.50	1.00	5.00	7.50	7.50		7.50							
	WALL TILES	SFT	1	2.00	1.00	5.00	10.00	10.00		10.00							
	WALL TILES	SFT	1	2.58	1.00	5.00	12.92	12.92		12.92							
	WALL TILES	SFT	2	0.50	1.00	5.00	5.00	5.00		5.00							
B	LADIES TOILET																
1	FLOORING	SFT	1	4.50	4.00	1.00	18.00	18.00	18.00								
	FLOORING	SFT	1	2.50	0.50	1.00	1.25	1.25	1.25								
	WALL TILES	SFT	1	4.00	1.00	5.00	20.00	20.00		20.00							
	WALL TILES	SFT	1	5.00	1.00	5.00	25.00	25.00		25.00							
	WALL TILES	SFT	1	4.50	1.00	5.00	22.50	22.50		22.50							
	WALL TILES	SFT	1	0.50	1.00	5.00	2.50	2.50		2.50							
	WALL TILES	SFT	1	1.50	1.00	5.00	7.50	7.50		7.50							
	TOILET																
2	FLOORING	SFT	1	5.00	4.21	1.00	21.04	21.04	21.04								
	FLOORING	SFT	1	2.50	0.50	1.00	1.25	1.25	1.25								
	WALL TILES	SFT	1	5.00	1.00	5.00	25.00	25.00		25.00							
	WALL TILES	SFT	1	4.21	1.00	5.00	21.04	21.04		21.04							
	WALL TILES	SFT	1	4.50	1.00	5.00	22.50	22.50		22.50							
	WALL TILES	SFT	1	0.50	1.00	5.00	2.50	2.50		2.50							
	WALL TILES	SFT	1	2.00	1.00	5.00	10.00	10.00		10.00							
	WASH BASIN AREA																
3	FLOORING	SFT	1	8.71	4.00	1.00	34.83	34.83	34.83								
	WALL TILES	SFT	1	8.71	1.00	5.00	43.54	43.54		43.54							
	WALL TILES	SFT	1	4.00	1.00	5.00	20.00	20.00		20.00							
	WALL TILES	SFT	1	1.00	1.00	5.00	5.00	5.00		5.00							
	WALL TILES	SFT	1	0.50	1.00	5.00	2.50	2.50		2.50							
	WALL TILES	SFT	1	1.50	1.00	5.00	7.50	7.50		7.50							
	WALL TILES	SFT	1	2.00	1.00	5.00	10.00	10.00		10.00							
	WASH BASIN AREA																
4	FLOORING	SFT	1	6.51	3.50	1.00	22.78	22.78	22.78								
	WALL TILES	SFT	1	6.51	1.00	5.00	32.54	32.54		32.54							
	WALL TILES	SFT	1	3.50	1.00	5.00	17.50	17.50		17.50							
	WALL TILES	SFT	1	3.51	1.00	5.00	17.54	17.54		17.54							
	TOTAL						774.30	190.20	584.11	0.00	0.00	0.00					774.30
	40MM THICK GRANITE PLATFORM FOR WASH BASIN & SERVICE PLAT FORM																
	G.F	SFT	1	12.00	2.00	1.00	24.00	24.00									
	G.F	SFT	1	4.00	2.00	1.00	8.00	8.00									
	G.F	SFT	1	2.75	2.00	1.00	5.50	5.50									
	FF	SFT	3	4.00	2.00	1.00	24.00	24.00									
	SF	SFT	2	4.00	2.00	1.00	16.00	16.00									
	TOTAL						77.50										77.50
	TOTAL						4645.58		0.00	12.50	0.00	0.00	77.50				90.00
	LIFT WALL GRANITE CLADDING																
	GF WALL	SFT	1	8.00	1.00	11.00	88.00	88.00									
	FF WALL	SFT	1	8.00	1.00	11.00	88.00	88.00									
	SF WALL	SFT	1	8.00	1.00	11.00	88.00	88.00									
	TOTAL						264.00										264.00
	TOTAL						8031.03		681.57	2070.42	0.00	291.97	264.00	1524.12			3307.96
									TOILET		KITCHEN		LIFT	DINING HALL			
									FLOORING	WALL TILES	FLOORING	WALL TILES	WALL TILES	FLOORING			

