ESTIMATION FOR FURNISHING WORKS OF CHITHRADURGA RO, KARNATAKA GRAMIN BANK, CHITHRADURGA.

GENERAL MAIN SPECIFICATION SHALL BE CONSIDERED FOR ALL ITEMS.

The Commercial boards used should be made of 19mm MR grade commercial board with both or single side 1mm thick laminated finish. Ply wood used for Storage unit rear side, partion wall inner and outer side and drawer and cupboard bottom which shall be provided with 6 mm MR grade commercial plywood with finish with 1mm thick laminate on one side per sheet and other side to be painted. The boards and laminate make and colours for the counter, table top, vertical sides, drawer, cupboard,storage unit,bands, skirting ,partion wall customer writing table,Notice board, Suggestion box etc shall be strictly as per the recommended brand and approved colours indicated by Bank . All the exposed edges of the Commercial boards shall be provided with teak wood beadings of required size or 1" x .5"with neatly finished with sand paper and with touchup putty and polished with proper number (3 coats) of coats of melamine polish. The hidden surfaces to be painted with one coat of anti termite wood primer and two coats of enamel painting of approved colour and make of the paints. All the exposed edges shall be lipped with 1"X0.5" or matching width Teak Wood Beading & neatly finished with sand paper and with touchup putty and polished with proper number (3 coats) of coats of melamine polish & stained to required colour shall be provided. Tables and staff table shall be provided with required no of round holes of 2.5" size with PVC cap at the required location for wire management etc. complete, Staff Tables and office counters shall be provided with two drawers minimum size of 13.5"x 22"x 5" (internal dimensions) fixed in between the intermediate support and main support, at every maximum of 5 ft c/c. main supports are provided for each counter and opposite side covered upto table top with Commercial boards used should be made of 19mm MR grade commercial board with front side 1mm thick laminated finish, the portion below the drawers shall have a cupboard with front shutter, providing and fixing 100mm 'C' type stainless steel handles, multipurpose locks, automatic steel Zero crank hinges for cupboards, the drawers to be provided with sliding channels etc.For every seating area staff tables and tables in cabins there shall be a key board tray of minimum 21" x 18" size made of 19mm MR grade commercial board with top expose side 1mm thick laminated and fixed with telescopic type metal channels fixed on the lower side of the counter/table top, For every seating area of tables and counters a foot rest of 3" x 2" Seasoned hard wood section with proper no of (3 coats) coats of melamine polish shall be provided on the lower side of the counter/table top. The front elevation of the office counter, partition wall shall be as per the design detailed in the drawing or as detailed by the Architect/ Engineer in-charge using the front elevation of the counter / partion shall be as per the design detailed in the drawing using 6mm thick design teak wood material to provide recession and finished with 1mm laminate. Handles and other hardware items and other items have to be used as per banks approved list of material/ banks prior approval, etc.complete. The rate quoted should include cost and conveyance of all materials,labour for all items of work,HOM as per specification. rest of specifications same as MAIN specifications and approved list of brand and approved list of materials shall be for all items, including tax,Complete to the satisfaction of the Engineer / Bank as per design/ drawing enclosed.

SL NO	DESCRIPTION OF ITEM OF WORKS	UNIT	TOTAL QTY	RATE	AMOUNT
1	**WOODEN CUM PARTITION FOR HALF CABIN, STORE ROOM, RECORDS ROOM , RM & CM CABIN & CUBICALS PARTITION :-**				
	Providing and fixing of double skin partition using new alluminium rectangular sections of 2.5" x 1.5" size with 1.70 mm thickness with verticals at a maximum spacing of 2 ft. C/C and five horizontals at 0', 3', 7', false ceiling & true ceiling level.The corner verticals shall be common.The partition shall be covered by 6mm thick MR grade commercial plywood of approved brand termite and water resistant. on both sides for the bottom and the top panel. The middle panel to be covered by 12mm thick plain glass fixed with 8mm thick teak wood beadings of necesary width. All the exposed surface of alluminium sections shall be covered by 6mm thick MR grade commercial grade plywood of approved brand termite and water resistant. & finished with 1mm thick lamination of approved make, quality & Colour . All the accessories used shall be of concealed type.The finishing for plywood shall be with 1mm thick lamination of approved shade on exposed sides & the hidden surfaces to be painted with one coat of anti termite wood primer and two coats of enamel painting of approved colour and make of the paints. All the exposed edges shall be provided with teak wood beadings of required size with finishing with sand paper and with touchup putty and polished with proper number (3 coats) of coats of melamine polish. There shall be 4" height skirting in the top and bottom on both sides with 1mm lamination finish. Necessary door shall be provided, The partition shall have required number of Doors (maximum of 3 number per partition) with Size 0.915m x 2.15m & 1.22m X 2.15m with Proper Hinges, Stoppers Locks, Handles, Hydraulic Closure etc., complete. edges shall be finished with teak wood beadings. All the exposed wood / wooden beadings shall be neatly finished with 3 coats of wood polish & stained to required colour. All the glass surfaces shall covered on one side as per the design by frosted film of approved make. The lamination shall be provided upto the false ceiling level. Necessary openings must be made in the frame sections to run the wires, computer cables wherever necessary with PVC cap. Similarly necessary cuttings to be made in the partition to fix switch boxes of electrical, telephone sockets, computer Information outlets, making provision for laying conduit;The rate include Provision of extra frame work as necessary verticle and horizantal members to be taken upto RCC ceiling joined with a horizontal memeber at top and for skirting,etc. complete. The general main specification and approved list of brand and approved list of materials shall be considered for design, elevation, specification ,make,colour,of items,quantity of items,material of items for commercial board, commercial ply wood, lamination, teak wood section,glass,beading ,fittings,hardware items ,paintings,wood polish, labour, rate etc. complete . Measurement of height should be up to false ceiling level & in case of only RCC roof ceiling measurement of height should be up to lamination top level .				
	HALF CABIN				
	a.) 1 NO X 4'1"X 4'				
	b.) 1 NO X 10'2"X 4'				
	c.) 2 NO X 10' X 4'				
	d.) 1 NO X 35'6" X 4'				
	LOBBY				
	a.) 1 NO X 5'1"X 9'6"				
	b.) 1 NO X 2'7" X 9'6"'				
	STORE ROOM				
	a.) 1 NO X 16'9"X 9'6"'				
	b.) 1 NO X 5'8" X 9'6"'				

	RECORD ROOM				
	a.) 1 NO X 19'6"X 9'6"'				
	b.) 1 NO X 22'1" X 9'6"'				
	RM CABIN				
	a.) 1 NO X 22'X 9'6"'				
	CM CABIN				
	a.) 1 NO X 10'10" X 9'6"'				
	CUBICALS				
	a.) 2 NO X 12' X 4'				
	b.) 17 NO X 5'10" X 4'				
	a.) 6 NO X 6' X 4'				
	b.) 1 NO X 5'8" X 4'				
	c.) 1 NO X 2' X 4'				
	d.) 2 NO X 35'4" X 4'				
	ITEM TOTAL QUANTITY	**Sq.ft**	**2221.75**		
2	**CUBICAL WORKING TABLE**				
	Providing and fixing CUBICAL WORKING TABLE of length 4.5' to 8' ,height 30" and top width 30" all minimum dimensions with front , working top and side supports with the Commercial boards made of 19mm MR grade commercial board with both or single side 1mm thick laminated finish. There shall be Two draws of size 16"x 22"x 5" fixed in a alround boxing with top and one of the side of the table as common top and side.The portion below the drawers shall have a cupboard with front shutter. All by using 19mm thick `MR grade commercial board with exposed side with 1mm thick laminated finish & the hidden surfaces to be painted with one coat of anti termite wood primer and two coats of enamel painting of approved colour and make of the paint except for draw bottom which shall be provided with 6 mm MR grade commercial plywood. . including providing and fixing 100mm 'C' type stainless steel handles, multipurpose locks, automatic steel Zero crank hinges for cupboards etc. The working top, sides,front face of draw shall be finished with exposed side with 1mm thick laminated finish. For every seating area there shall be a key board tray of minimum 21" x 18" size made of 19mm thick `MR grade commercial board with one side 1mm thick laminated , the hidden surfaces to be painted with one coat of anti termite wood primer and two coats of enamel painting of approved colour and make of the paints and fixed with telescopic type metal channels fixed on the lower side of the counter/table top, A foot rest of 3" x 2" Seasoned hard wood section with neatly finished with sand paper and with touchup putty and polished with proper number (3 coats) of coats of melamine polish . The draws shall have sliding arrangement by using readymade metal rollers in metal channel. All the exposed edges shall be provided with teak wood beadings of required size or 1" x .5"with neatly finished with sand paper and with touchup putty and polished with proper number (3 coats) of coats of melamine polish . The hidden surfaces to be painted with one coat of anti termite wood primer and two coats of enamel painting of approved colour and make of the paints. Each draw shall have stainless steel handle with a locking system for the two draw unit. Necessary openings for the access of the wires with plug shall be provided inclusive of working top and covered with PVC caps as per Drawing. At all ends & every partition with maximum of 5 ft c/c. main supports are provided for table and front side covered upto table top with Commercial boards used should be made of 19mm MR grade commercial board with one side 1mm thick laminated finish & The hidden surfaces to be painted with one coat of anti termite wood primer and two coats of enamel painting of approved colour and make of the paints. , The general main specification and approved list of brand and approved list of materials shall be considered for design, elevation, specification, make,colour,of items, quantity of items, material of items for commercial board, commercial ply wood, lamination,hard wood section, glass,beading ,fittings, hardware items ,paintings,wood polish, labour, rate etc. complete .				
	a.) 21 NO X 4'10" X 2'6"				
	b.) 1 NO X 4'4" X 2'6"				
	c.) 4 NO X 5'4"X 2'6"				
	ITEM TOTAL QUANTITY	**Sq.ft**	**317.92**		

3	**TABLE FOR HALF CABIN, RM CABIN & CM CABIN**				
	Providing and fixing TABLE of length 6' to 8' ,height 30" and top width 36" to 48" all minimum dimensions with front , working top and side supports with the Commercial boards made of 19mm MR grade commercial board with both or single side 1mm thick laminated finish & the hidden surfaces to be painted with one coat of anti termite wood primer and two coats of enamel painting of approved colour and make of the paints.. There shall be Two draws of size 16"x 22"x 5" fixed in a alround boxing with top and one of the side of the table as common top and side.The portion below the drawers shall have a cupboard with front shutter. All by using 19mm thick `MR grade commercial board with exposed side with 1mm thick laminated finish & the hidden surfaces to be painted with one coat of anti termite wood primer and two coats of enamel painting of approved colour and make of the paint except for draw bottom which shall be provided with 6 mm MR grade commercial plywood. . including providing and fixing 100mm 'C' type stainless steel handles, multipurpose locks, automatic steel Zero crank hinges for cupboards etc. The working top, sides,front face of draw shall be finished with exposed side with 1mm thick laminated finish. The working top shall be provided with 10mm thick clear glass edges biveled. For every seating area there shall be a key board tray of minimum 21" x 18" size made of 19mm thick `MR grade commercial board with one side 1mm thick laminated and fixed with telescopic type metal channels fixed on the lower side of the counter/table top, A foot rest of 3" x 2" Seasoned hard wood section with neatly finished with sand paper and with touchup putty and polished with proper number (3 coats) of coats of melamine polish . The draws shall have sliding arrangement by using readymade metal rollers in metal channel. All the exposed edges shall be provided with teak wood beadings of required size or 1" x .5"with neatly finished with sand paper and with touchup putty and polished with proper number (3 coats) of coats of melamine polish . The hidden surfaces to be painted with one coat of anti termite wood primer and two coats of enamel painting of approved colour and make of the paints. Each draw shall have stainless steel handle with a locking system for the two draw unit. Necessary openings for the access of the wires with plug shall be provided inclusive of working top and covered with PVC caps as per Drawing. At all ends & every partition main supports are provided for table and cusstomer side covered upto table top with Commercial boards used should be made of 19mm MR grade commercial board with one side 1mm thick laminated finish & The hidden surfaces to be painted with one coat of anti termite wood primer and two coats of enamel painting of approved colour and make of the paints. , The general main specification and approved list of brand and approved list of materials shall be considered for design, elevation, specification, make,colour,of items, quantity of items, material of items for commercial board, commercial ply wood, lamination, hard wood section, glass, beading , fittings, hardware items ,paintings,wood polish, labour, rate etc. complete .				
	HALF CABIN				
	a.) 3 NO X 6'6" X 3'6"				
	RM CABIN				
	b.) 1 NO X 8' X 4'				
	CM CABIN				
	c.) 1 NO X 7' X 3'6"				
	ITEM TOTAL QUANTITY	**Sq.ft**	**124.75**		
4	**MINERAL FIBRE BOARD GRID TYPE FALSE CEILING**				
	Providing, fabricating,erecting lay-intype tegular/droptype Mineral fibre board false Ceiling of 600mmx600mm grid asper the following specifications.The approved brands are ARMSTRONG or Tiles of Saint Gobain Mineral Fibre Acoustic Ceiling Tiles. The following specifications are the minimum and tenderers may quote for the equivalent or better specification. The grid system having 600 mm x 600 mm or part there of wherever necessary, shall be made using hot dipped galvanized steel section, exposed surface chemically cleaned capping prefinished in backed polyester paint of approved colour, main Tee of size 14 x 38 x 0.33 mm at every 1200 mm c/c max and rotary stitched cross tee of size 14 x 38 x 0.33 mm at every 600 mm c/c and cross Tee of size 14 x 38 x 0.33 mm at every1 200 c/c max and 14 x 22 x 0.457 mm wall angle alround the wall to form grid size of 600 x 600 mm. The suspension system shall have 4mm dia pre straightened Gl rods which are in-turn supported from real ceiling using 6 mm size anchor bolts, connected with adjustable Hanger clips / Jbolts and other accessories as per the manufacturers specifications. The T Sections have a Galvanizing of 120 grams per M2 & passed through for 500 hrs of Salt test. The tiles/panels shall be of prima Fine Fissured Microlook tegular of ARMSTRONG Mineral Fibre Acoustic CeilingTiles of size 600 x 600 x 18 mm thick over the formed grid, in module size of 600 mm x 600 mm x 18mm Thick. The item shall include the cost of additionalTee or L supports & other accessories near the ends / odd size edges / corners, making necessary openings for electrical light fittings, AC units, fire alarm detectors, other fittings and any other fixtures. No extra payement shall be made for making openings in the panels / grid for the purpose of light fittings. Item rate shall include all the taxes, transportation, erection, loading & unloading and any other incidental expenditure that may be required to be spent in completing the work in totality as per above specifications.The tiles removed to place light fittings shall be handed over to bank's custody and there may not be any deduction for light fittings area.The general main specification and approved list of brand and approved list of materials shall be included.				
	ITEM TOTAL QUANTITY	**Sq.ft**	**2700.00**		

5	**STORAGE UNITS FOR HALF CABINS, RM CABIN, CM CABIN , CUBICALS & UPS ROOM**				
	Providing and fixing storage units with DEPTH of 18" with necessary swinging shutters, all made of 19mm thick MR grade commercial board with external side 1mm thick laminated finish & the internal surfaces & hidden surfaces to be painted with one coat of anti termite wood primer and two coats of enamel painting of approved colour and make of the paints to be provided for internal surfaces of sides, partitions, top, shelves, bottom, shutters. The exposed surfaces including rear side shall be finished with 1mm thick lamination of approved shade & brand. Unit shall have internally required horizontal shelves and vertical partitions all made with 19mm thick `MR grade commercial board with both side surfaces to be painted with one coat of anti termite wood primer and two coats of enamel painting of approved colour and make of the paints. . All the exposed edges shall be lipped with1"x1/2" matching Wood Beading & neatly finished with sand paper and with touchup putty and polished with proper number (3 coats) of coats of melamine polish . 12mm thick MR grade commercial plywood to be fixed for the rear side in side covered with external surface with 1 mm thick lamination finish. The shutters shall have locking arrangement , 3" size stainless steel handles, Ball catch,automatic steel Zero crank hinges for cupboards, 3" PC Aluminium Tower bolts as per the requirement. The general main specification and approved list of brand and approved list of materials shall be considered for design, elevation, specification, make, colour,of items, quantity of items,material of items for commercial board,commercial ply wood, lamination,hard wood section,glass,beading ,fittings,hardware items ,paintings, wood polish, labour, rate etc. complete . (DEPTH=18") Measurement will be based on front surface area length & height measurements of storage units.				
	HALF CABIN				
	a.) 3 NO X 3' X 2'6"				
	RM CABIN				
	b.) 1 NO X 8' X 2'6"				
	c.) 1 NO X 6'6" X 2'6"				
	d.) 1 NO X 5'6" X 2'6"				
	CM CABIN				
	f.) 1 NO X 8' X 2'6"				
	f.) 1 NO X 2'11" X 2'6"				
	CUBICALS				
	g.) 1 NO X 5'4" X 4'				
	h.) 1 NO X 5'8" X 4'				
	i.) 1 NO X 3' X 4'				
	PASSAGE				
	j.) 1 NO X 3' X 7'				
	UPS ROOM				
	k.) 1 NO X 3' X 7'				
	ITEM TOTAL QUANTITY	**Sq.ft**	**197.79**		
6	**POSTAL TAPAL UNIT (DEPTH=15")**				
	Providing and fixing postal tapal unit with DEPTH of 15" with necessary horizontal & vertical partitions & swinging shutters for Cupboards with height of 15" to be provided at bottom of postal tapal unit , with 140 number of tapal boxes , each tapal box width & height 9", all sides made of 19mm thick MR grade commercial board with external side & internal side 1mm thick laminated finish & hidden surfaces to be painted with one coat of anti termite wood primer and two coats of enamel painting of approved colour and make of the paints to be provided. 19mm thick MR grade commercial board to be provided for sides, partitions, top, shelves, bottom, shutters. The exposed surfaces including rear side shall be finished with 1mm thick lamination of approved shade & brand. Unit shall have internally required horizontal shelves and vertical partitions all made with 19mm thick `MR grade commercial board with both side surfaces to be finished with 1mm thick laminate . All the exposed edges shall be lipped with1"x1/2" matching Wood Beading & neatly finished with sand paper and with touchup putty and polished with proper number (3 coats) of coats of melamine polish . 12mm thick MR grade commercial plywood to be fixed for the rear side both sides surface covered with 1 mm thick lamination finish. Cupboards with height of 15" to be provided at bottom of postal tapal unit with necessary horizontal & vertical partitions & swinging shutters , the cupboards shutters shall have locking arrangement , 3" size stainless steel handles, Ball catch, automatic steel Zero crank hinges , 3" PC Aluminium Tower bolts as per the requirement. The general main specification and approved list of brand and approved list of materials shall be considered for design, elevation, specification, make, colour,of items, quantity of items,material of items for commercial board,commercial ply wood, lamination,hard wood section, beading , fittings, hardware items , paintings, wood polish, labour, inculded in rate, etc. complete . (DEPTH=15") Measurement will be based on front surface area length & height measurements of postal tapal units.				
	a.) 1 NO X 10' X 9'				
	ITEM TOTAL QUANTITY	**Sq.ft**	**90.00**		

7	**SOLID WOODEN PARTITION USING NEW ALLUMINIUM SECTIONS, 6MM PLY WOOD ON OUTER SIDE & 8MM THICK BISON BOARD ON THE INNER SIDE (UPS ROOM)**				
	Providing and fixing double skin partition using new alluminium rectangular sections of 2.5" x 1.5" size with 1.70mm thickness, with verticals at a maximum spacing of 2ft. c/c in both directions.The corner verticals shall be common.The partition shall be covered by 6mm MR grade commercial thick ply wood on outer side and 8 mm thick bison board on the inner side (UPSside) .The finishing shall be with 1mm thick lamination of approved shade on plywood side & the bison board and hidden surfaces to be coated with surfaces to be painted with one coat of anti termite wood primer and two coats of enamel painting of approved colour and make of the paints with one coat of anti termite wood primer and two coats of enamel painting of approved colour and make of the paints.. All the exposed wood/ woden beadings shall be neatly finished with sand paper and with touchup putty and polished with proper number (3 coats) of coats of melamine polish . & stained to required colour. There shall be a 4" height skirting in the top and bottom on lamination finish side. Necessary openings for the door shall be provided which shall be finished with beach wood beadings. The lamination shall be provided upto the falseceiling level. The partition shall have 1 Doors with Size 0.9m x 2.13m with Proper Hinges, Stoppers Locks, Handles, Hydraulic Closure etc., complete.Necessary openings must be made in the frame sections to run the wires, computer cables wherever necessary with PVC cap. Similarly necessary cuttings to be made in the partition to fix switch boxes of electrical, telephone sockets, computer Information outlets, making provision for laying conduit;The rate include Provision of extra frame work as necessary verticle and horizantal members to be taken upto RCC ceiling joined with a horizontal memeber at top and for skirting,etc. complete. The general main specification shall considered for design, elevation, specification , make, colour,of items,quantity of items,material of items for commercial board, commercial ply wood, lamination,hard wood section, glass, beading , fittings, hardware items , paintings,wood polish, rate etc. complete . Measurement of height should be up to false ceiling level & in case of only RCC roof ceiling measurement of height should be up to lamination top level .				
	UPS ROOM				
	a.) 1 NO X 16'9" X 9'6"				
	b.) 1 NO X 6' X 9'6"				
	c.) 1 NO X 6'4"X 9'6"				
	ITEM TOTAL QUANTITY	**Sq.ft**	**276.29**		
8	**INTERNAL WALL & CEILING RE PAINTING WITH EMULSION**				
	INTERIOR PAINT : Wall & Ceiling painting with 2 coats of premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 g/L of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour over 2 coats of putty & 1 coat of primer. Providing and applying white cement based 2 coat of putty to provide average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as per specifications and as per directions of Engineer in charge. Applying priming coat with 1 coat of primer of approved brand and manufacture, having low VOC (Volatile Organic Compound) content. 2 coats premium acrylic emulsion paint as per specifications and to give an even appproved shade after throughly brushing the surface, free from mortor drops & other freign matter including preparing the surface even with sand paper including cost of materials, labour scaffolding etc., complete as per directions of Engineer in charge. and Specifications as per KPWD SR SL NO 8.54.2 , 8.55.1, 8.51 VOL2 PAGE 50 , etc. complete.				
	RO HALL, STAIRCASE, STORE, RECORDS ROOM, UPS				
	1 NO X 300' X 9'6"				
	TOILET WALLS				
	1 NO X 69'6" X 5'				
	CEILING OF STAIRCASE, STORE, RECORDS ROOM, UPS, TOILET				
	1 NO X 1200 SFT				
	ITEM TOTAL QUANTITY	**Sq.ft**	**4397.50**		

9	**REMOVAL OF EXISTING WOODEN CUM PARTITION, CUBICAL WORKING TABLE, TABLE FOR CABINS, STORAGE UNITS, POSTAL TAPAL UNIT, SOLID WOODEN PARTITION , MINERAL FIBRE BOARD GRID TYPE & GYPSM BOARD FALSE CEILING, SOLID WOODEN PARTITION USING 6MM PLY WOOD ON OUTER SIDE & 8MM THICK BISON BOARD ON THE INNER SIDE (UPS ROOM), DOORS TO BE REMOVED**				
	Taking out above existing interior furniture and partitions including stacking to the appropriate disposal area & repairing the damaged edges of the existing flooring with similar flooring, brick work / cement block work with cement morter (1:3) & repainting the same with 2 coats of premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 g/L of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour over 2 coats of putty & 1 coat of primer as per direction of bank and Architect including cost of materials, labour scaffolding etc. complete. The schedule of removal of existing furniture & partition should be approved by Bank and Architect. The removal of existing interior furniture should not disturb the Regional office daily work.	lumpsum			
	Total				
	GST 18 %				
	Grand Total				

ESTIMATION FOR FURNISHING WORKS OF CHITHRADURGA RO, KARNATAKA GRAMIN BANK, CHITHRADURGA.

ANNEXURE 1

SL NO	ITEM	UNIT	NO	LENGTH			WIDTH			HEIGHT			QTY	TOTAL QTY
				FEET	INCH	TOTAL	FEET	INCH	TOTAL	FEET	INCH	TOTAL		
1	**WOODEN CUM PARTITION FOR HALF CABIN, STORE ROOM, RECORDS ROOM , RM & CM CABIN & CUBICALS PARTITION :-**													
A	HALF CABIN													
a	a.) 1 NO X 4'1"X 4'	Sqft	1	4	1	4.08				4	0	4	16.33	
b	b.) 1 NO X 10'2"X 4'	Sqft	1	10	2	10.17				4	0	4	40.67	
c	c.) 2 NO X 10' X 4'	Sqft	2	10	0	10.00				4	0	4	80.00	
d	d.) 1 NO X 35'6" X 4'	Sqft	1	35	6	35.50				4	0	4	142.00	
B	LOBBY													
a	a.) 1 NO X 5'1"X 9'6"	Sqft	1	5	1	5.08				9	6	9.5	48.29	
b	b.) 1 NO X 2'7" X 9'6"'	Sqft	1	2	7	2.58				9	6	9.5	24.54	
C	STORE ROOM													
a	a.) 1 NO X 16'9"X 9'6"'	Sqft	1	16	9	16.75				9	6	9.5	159.13	
b	b.) 1 NO X 5'8" X 9'6"'	Sqft	1	5	8	5.67				9	6	9.5	53.83	
D	RECORD ROOM													
a	a.) 1 NO X 19'6"X 9'6"'	Sqft	1	19	6	19.50				9	6	9.5	185.25	
b	b.) 1 NO X 22'1" X 9'6"'	Sqft	1	22	1	22.08				9	6	9.5	209.79	
E	RM CABIN													
a	a.) 1 NO X 22'X 9'6"'	Sqft	1	22	0	22.00				9	6	9.5	209.00	
F	CM CABIN													
a	a.) 1 NO X 10'10" X 9'6"'	Sqft	1	10	10	10.83				9	6	9.5	102.92	
G	CUBICALS													
a	a.) 2 NO X 12' X 4'	Sqft	2	12	0	12.00				4	0	4	96.00	
b	b.) 17 NO X 5'10" X 4'	Sqft	17	5	10	5.83				4	0	4	396.67	
a	a.) 6 NO X 6' X 4'	Sqft	6	6	0	6.00				4	0	4	144.00	
b	b.) 1 NO X 5'8" X 4'	Sqft	1	5	8	5.67				4	0	4	22.67	
c	c.) 1 NO X 2' X 4'	Sqft	1	2	0	2.00				4	0	4	8.00	
d	d.) 2 NO X 35'4" X 4'	Sqft	2	35	4	35.33				4	0	4	282.67	
	TOTAL OF WOODEN CUM PARTITION FOR HALF CABIN, STORE ROOM, RECORDS ROOM , RM & CM CABIN & CUBICALS PARTITION	Sqft											2221.75	2221.75
2	**CUBICAL WORKING TABLE**													
a	a.) 21 NO X 4'10" X 2'6"	Sqft	21	4	10	4.83	2.0	6.0	2.5				253.75	
b	b.) 1 NO X 4'4" X 2'6"	Sqft	1	4	4	4.33	2.0	6.0	2.5				10.83	
c	c.) 4 NO X 5'4"X 2'6"	Sqft	4	5	4	5.33	2.0	6.0	2.5				53.33	
	TOTAL OF CUBICAL WORKING TABLE	Sqft											317.92	317.9
3	**TABLE FOR HALF CABIN, RM CABIN & CM CABIN**													
	HALF CABIN													
a	a.) 3 NO X 6'6" X 3'6"	Sqft	3	6	6	6.50	3	6	3.5				68.25	
	RM CABIN													
b	b.) 1 NO X 8' X 4'	Sqft	1	8	0	8.00	4	0	4.0				32.00	
	CM CABIN													
c	c.) 1 NO X 7' X 3'6"	Sqft	1	7	0	7.00	3	6	3.5				24.50	
	TOTAL OF TABLE FOR HALF CABIN, RM CABIN & CM CABIN												124.75	124.8

4	**MINERAL FIBRE BOARD GRID TYPE FALSE CEILING**													
a		Sqft	1										2700.00	
	TOTAL OF MINERAL FIBRE BOARD GRID TYPE FALSE CEILING												2700.00	2700.00
5	**STORAGE UNITS FOR HALF CABINS, RM CABIN, CM CABIN , CUBICALS & UPS ROOM (DEPTH=18")**													
	HALF CABIN													
a	a.) 3 NO X 3' X 2'6"	Sqft	3	3	0	3.00				2	6	2.5	22.50	
	RM CABIN													
b	b.) 1 NO X 8' X 2'6"	Sqft	1	8	0	8.00				2	6	2.5	20.00	
c	c.) 1 NO X 6'6" X 2'6"	Sqft	1	6	6	6.50				2	6	2.5	16.25	
d	d.) 1 NO X 5'6" X 2'6"	Sqft	1	5	6	5.50				2	6	2.5	13.75	
	CM CABIN													
e	f.) 1 NO X 8' X 2'6"	Sqft	1	8	0	8.00				2	6	2.5	20.00	
f	f.) 1 NO X 2'11" X 2'6"	Sqft	1	2	11	2.92				2	6	2.5	7.29	
	CUBICALS													
g	g.) 1 NO X 5'4" X 4'	Sqft	1	5	4	5.33				4	0	4	21.33	
h	h.) 1 NO X 5'8" X 4'	Sqft	1	5	8	5.67				4	0	4	22.67	
i	i.) 1 NO X 3' X 4'	Sqft	1	3	0	3.00				4	0	4	12.00	
	PASSAGE													
j	j.) 1 NO X 3' X 7'	Sqft	1	3	0	3.00				7	0	7	21.00	
	UPS ROOM													
k	k.) 1 NO X 3' X 7'	Sqft	1	3	0	3.00				7	0	7	21.00	
	TOTAL OF STORAGE UNITS FOR HALF CABINS, RM CABIN, CM CABIN , CUBICALS & UPS ROOM												197.79	197.8
6	**POSTAL TAPAL (DEPTH=15")**													
a	a.) 1 NO X 10' X 9'	Sqft	1	10	0	10.00				9	0	9	90.00	
	TOTAL OF TAPAL UNIT												90.00	90.0
7	**SOLID WOODEN PARTITION USING NEW ALLUMINIUM SECTIONS, 6MM PLY WOOD ON OUTER SIDE & 8MM THICK BISON BOARD ON THE INNER SIDE (UPS ROOM)**													
	UPS ROOM													
a	a.) 1 NO X 16'9" X 9'6"	Sqft	1	16	9	16.75				9	6	9.5	159.13	
b	b.) 1 NO X 6' X 9'6"	Sqft	1	6	0	6.00				9	6	9.5	57.00	
c	c.) 1 NO X 6'4"X 9'6"	Sqft	1	6	4	6.33				9	6	9.5	60.17	
	TOTAL OF SOLID WOODEN PARTITION USING NEW ALLUMINIUM SECTIONS, 6MM PLY WOOD ON OUTER SIDE & 8MM THICK BISON BOARD ON THE INNER SIDE (UPS ROOM)												276.29	276.3
8	INTERNAL WALL & CEILING RE PAINTING WITH EMULSION													
a	RO HALL, STAIRCASE, STORE, RECORDS ROOM, UPS													
	1 NO X 300' X 9'6"	Sqft	1	300	0	300.00				9	6	9.5	2850.00	
b	TOILET WALLS													
	1 NO X 69'6" X 5'	Sqft	1	69	6	69.50				5	0	5	347.50	
c	CEILING OF STAIRCASE, STORE, RECORDS ROOM, UPS, TOILET													
	1 NO X 1200 SFT	Sqft	1										1200.00	
	TOTAL OF INTERNAL WALL RE PAINTING WITH EMULSION												4397.50	4397.5