Specifications and Schedule of Work

Sl No.	Description of work	Qnty	Rate	Amount
1.	**Wooden cum Glass Partition for Manager Cabin :-** Providing, Fabricating & Fixing Partition frame consisting of 50x50mm Sal wood frame at spacing not exceeding 600mm c/c fixed to the bottom & ceiling. The Partition shall be skinned on both faces with 6mm commercial ply wood of approved brand termite and water resistant. Exterior faces to be pasted with 1mm thick laminate of approved quality &Colour to the top & bottom Panels of the Partition, middle panel to be covered with 6mm thick plain glass with itching of 5mm thick line at every125mm c/c both ways firmly fixed. The partition shall have 2Nos. of Doors Size 0.91m x2.13m with Proper Hinges, Stoppers Locks, Handles, Hydraulic Closure etc., complete. **Note : Ceiling height 3.05 m from floor level** **1 No. x 10'2" x 10'0"= 101.70 Sft** **1 No. x 10'8" x 10'0"= 106.70 Sft** **1 No. x 10'6" x 10'0"= 105.00 Sft** **Total Area = 313.40 Sft**	**313.40 Sft**		
2.	**Partition for Single Window Counter :-** Providing & fixing cash cabin partition using Seasoned Sal Wood Frame not less than 75mmx50mm in size firmly fixed to the table, providing and fixing 6mm plain glass with itching works firmly fixed using Teak wood beadings with provision of of size above sections above firmly fixed to the floor with 9mm thick interior grade pre-laminated board of approved shade up to 1.21m height above with 5mm thick plain glass, The partition shall have 1no. Door of size 0.90m x 1.52 with doors with proper hinges stoppers, locks, handles, etc., complete. **For Front above the table:-** **– 1 No. x 6'0" x 4'6"= 27.00 Sft** **For Side – 1 No. x 3'0" x 4'6"= 13.50 Sft** **– 1 No. x 6'0" x 7'0"= 42.00 Sft** **Total Area = 82.50 Sft**	**82.50 Sft**		

3.	**<u>Clerical Low counter :-</u>** Providing and fixing in position of low counter using 19mm thick (BWR) marine grade plywood for front side and for all other sides top shall be provided with 19mm thick (BWR) marine grade plywood, there shall be three drawer at every 134 cm c/c arrangements shall be made for key board trays with telescopic sliding channels and CPU stand at every 134 cm c/c/ all exterior and top panel to be provided with 1mm thick mate finish laminate of approved make and shade, and internal surfaces with white colour Laminated Sheet, Multipurpose locks , 100mm 'C' type stainless steel handles shall be provided for drawer & cupboards. Laminated/Teakwood footrest of size 75mmx 38mm the front side counter edges / ends to be provided with 50mm diasemi circular teak wood beading with PU coating system. Cable managers for counter top. The height of the counter 75cm, width of the counter 90cms including cost of all materials, transportations, labour etc., complete, as per design / drawing enclosed. **Low Counter** **1 No. x 6'0" x 3'0" = 18.00 Sft** **3 Nos. x 5'0" x 3'0" = <u>45.00</u> Sft** **Total Area = 63.00 Sft** **Printer Table –** **1 No. x 2'7" x 3'0" = 07.74 Sft**	**63.00 Sft** **07.74 Sft**		
4.	**<u>Manager's Works Station:-</u>** Providing and fixing in position of managers work station with side runner using 19mm thick (BWR) marine grade plywood for all the sides and finished with 1mm thick laminate of approved make and shade (lamination to be done for all outer portions and inner surfaces with internal lamination of approved colour. The drawers to be provided with sliding channels. Inner portion of drawers, cupboards finished with internal lamination of approved colour. Front side edges to be finished with 50mm dia semicircular teak wood beading finished with Polish and rear edges to be provided with 20mm x 6mm teak wood beading finished with Polish including providing and fixing 100mm 'C' type stainless steel handles, Godrej multipurpose locks, automatic steel Zero crank hinges for cupboards etc, table and runner top laid with 10mm thick plain glass including fixing keyboard with telescopic sliding channel, CPU stand 75 x 38mm teak wood footrest etc., complete as per design/ drawing enclosed. **Table –1No. x 7'0" x 3'0" = 21.00 Sft** **–1No. x 4'0" x 2'0" = <u>08.00</u> Sft** **Total Area = 29.00 Sft**	**29.00 Sft**		

5.	**<u>Storage Unit Cabinet Type:-</u>** Providing and fixing storage system of 1.5' Depth or required length and depth of the cabinate made with 18mm commercial board of approved make with ISI mark. The top sides and front face of the cabinate have to the pasted with 1mm thick laminated sheet. The cabinate should have required nos. of shelves/ with doors fitted with good quality Hinges and locking arrangements, with magnet catch for rack type storage units more No.s of Selves and partition to be provided. All the edges of the cabinet should be provided with TW / beech wood beadings with two coats of melamine polish and inner surface / and the back side of the cabinet have to be painted with two coats of wood primer and two coats of enamel painting of approved colour and make of the paints the colour of the laminated sheets, handles and other hardware items have to be used as per banks approved list of material / banks prior approval. **Side Box for Cash Counter –** **01 No. x 03'3" x 1'6"= 4.88 Sft** **Storage @ Stationaries Room –** **01 No. x 13'0" x 7'0"= <u>91.00</u> Sft** **Total Area = 95.88 Sft**	**95.88 Sft**		
6.	**<u>Glass Partition:-</u>** Providing and fixing 12mm glass partition to low counters with proper bracketing and hinged with vertical wooden post. **Officer & Clerical Low Counter** – **03 Nos. x 05'0" x 1'6"= <u>22.50</u> Sft** **Total Area = 22.50 Sft**	**22.50 Sft**		
7.	**<u>Aluminium Deco Grill:-</u>** Providing and fixing Aluminium Deco Grill to the Cash Counter top. **Cash Counter** – **01 No. x 06'0" x 9'0"= 54.00 Sft**	**54.00 Sft**		
8.	**<u>Flap Gate :-</u>** Providing and fixing of position of flap gate made out of 19mm thick (BWR) marine grade plywood and exposed portions to be laminated with 1mm thick laminate of approved make and shade for both surfaces. Edges to be provided with Teak wood beading, including cost of all materials, labour etc., complete. **Flap Gate- 1No. x 2'6" x 2'6" = 06.25 Sft**	**06.25 Sft**		

9.	**<u>Customers Writing Table :-</u>** Providing and fixing wall mounted writing table using 12mm thick (BWR PF Bonded) marine graded plywood and exposed surfaces shall be provided with 1mm thick laminate of approved make and shade. There shall be dividers at every 200mm c/c inner surfaces to be applied with 2 coats of enamel paint over coat of primer and edges to be provided with decorative Teak wood beading. Table size length x 0.30 m x 0.23 m including cost of all materials, labour charges with MS angle support of size 35mm x 35mm x 4mm etc., complete.	**1 No.**		
10.	**<u>Notice Board:-</u>** Providing and fixing Notice board of size 3'0" x 2'0" by using 18mm thick marine plywood and exposed surfaces shall be provided with 1mm thick lamination of approved make and colour.	**1 No.**		
11.	**<u>Poster Frame :-</u>** Providing and fixing poster frame fabricated using 2 sheets of 36"x 24" clear acrylic.Outer sheet should be 5 mm thick and bevelled crystal edge polished for 3/ 4" at 8-10 degrees on all sides in the front.Rear sheet should be 5 mm and flat.	**3 No.**		

Total

Rupees:

Name and Address
Of the Contractor

Witness: